

Maria Chapman School

Weymouth, Massachusetts



General Contractor:

Bond Brothers

Engineer:

Garcia Galuska DeSousa

Architect:

HMFH Architects

Owner:

Town of Weymouth

Contract Price:

\$14,175,900

Duration:

20 Months

SERVICES:

HVAC

Harold Brothers Mechanical performed the HVAC scope of work for the Maria Weston Chapman Middle School project in Weymouth. This scope included 415 tons of cooling between (2) aircooled chillers, (17) custom rooftop units as well as a pre-fabricated mechanical penthouse with (3) 5,000 MBH boilers and (10) hydronic pumps. The interior of the building featured (487) installed radiant units as well as (213) VAV boxes, all associated piping, ductwork, insulation and temperature controls.



Plumbing #12459